

CONCEPTS

The technology of the project was approached through a lens of emerging building technology. After conducting research on which EBTs the industry is currently involved with, 3D Concrete Printing was selected as the main technology focus of the project. This was done to promote the inclusion of a currently underdeveloped and high-tech EBT in an environment that would be directly exposed to the spatial designers in the build industry.

Concepts were the initial core of the technology development. Parti diagrams evolved into more complex sketches where the building technology became entangled with other structural systems.

The planning stage becomes more intricate in selecting exactly where the technology focus in the structure would be beyond the EBT. The 3DCP wall and roof connection of the auditorium was selected as the focus point. This would entail the connection between concrete and steel.

The lack of formwork in the construction process sets this technology apart from normal concrete construction. Less reinforcement is used in the walls as well, resulting in a less intensive use of additional resources to create the 3DCP walls.


Although the technology is not widely used in South Africa at the moment, this project becomes an opportunity to introduce the technology in an appropriate setting.

FOCUS ON ADDITIVE MANUFACTURING (3D CONCRETE PRINTING)


PARTI DIAGRAMS



3D Printed Concrete wall parti diagram in plan



3D Printed Concrete wall in section - levels of hierarchy




3D Printed Concrete wall detail section with adjacent gabion wall



Explorations of 3DCP wall with infill and foundation structure



3DCP applied to smaller structures with overhangs and pergolas




3DCP applied to larger structures - auditorium space used for main detail

PLANNING


SKETCHES

The focus for creating a detail was placed on the connection between the 3DCP wall and the steel roof structure. Following the sketches done during the planning stage, exploded isometric drawing were created in Revit and further developed later in the design. Two iterations were developed, the latter reflecting the internal wall structure.


a rough section through the auditorium wall with focus on the wall to roof connection of the 3DCP wall



connection detail drawing and wall section below




hand-drawn detail of wall to steel beam connection of roof



ITERATION 1


The internal rib structure of the wall didn't have an influence on the exterior skin of the building. Columns were too large in size and the placement of steel plates proved to be excessive in this iteration.



3DCP WALL - ITERATION 1




3DCP PLAN DETAIL




3DCP ASSEMBLY DETAIL SCALE 1: 10

ITERATION 2


The second iteration was more successful since the envelope started reflecting the inner structure of the 3DCP wall. Additive manufacturing as a construction process was more clearly communicated.



3DCP WALL - ITERATION 2




3DCP PLAN DETAIL



3DCP ASSEMBLY DETAIL SCALE 1: 10


CONSTRUCTION PROCESS

PROCESS DIAGRAM




3DCP PROCESS


3DCP NOZZLE




3DCP NOZZLE DIAGRAM



3D CONCRETE LAYER SECTION



3DCP STEPS



SUMMARY

ADVANTAGES


- DESIGN INNOVATION
- ACCURACY OF CONSTRUCTION
- CUTS DOWN ON MATERIAL WASTE
- REDUCES CONSTRUCTION TIME

DISADVANTAGES

- HIGHER COSTS
- REGULATION CHALLENGES
- SCARCITY OF EXPERTISE AND EQUIPMENT



ITERATION 1



Specification

IN-SITU CONCRETE (F)

F1 - MIXES/CASTING/CURING

F10 - In-situ concrete mixes / Casting / Curing

F10 100 In-situ concrete mix 36.8% cement, 3% perlite, 44.9% sand, 14.1% water, 0.8% superplasticizer, 0.4% accelerating admixture, 0.1% sodium silicate to be mixed on site and placed into pumping module

F10 101 Casting process concrete mix to be pumped module by screw feeder and printed from 125 nozzle in stacking layers

F10 102 Concrete layers printed in 25mm layers with 3 days minimum curing time, covered in polyethylene film

F3 - REINFORCEMENT

F30 - Steel reinforcement

F30 100 T10 steel rebars post-tensioned for in-situ rafter slabs

F4 - FINISHES/JOINTS/SUNDRIES

F40 - Design joints in in-situ concrete

F40 100 200mm fibre board expansion joint fillers to be inserted at joints between interior concrete surfaces and 3DCP walls

F5 - IN-SITU CONCRETE ELEMENTS

F50 - In-situ concrete foundations


F50 100 In-situ reinforced concrete rafter slab foundations created with in-situ 3DCP

F52 - In-situ concrete floors/ roof decks


F52 100 100 mm thick concrete floor created in-situ with 3DCP

F54 - In-situ concrete frames/ wall panels/ stairs

F54 100 25 x 50 mm layers of concrete mix with perlite filler printed with 3D concrete manufacturing gantry machine, with printed walls covered with polyethylene film after printing during curing process




SECTION A-A
SCALE 1:50



DETAIL 2
SCALE 1:20

DETAILS



SA PRIVATE SCHOOL - PRIMARY SCHOOL

PRIVATE PARKING SPACE

JOHANNES RAMOKHOASE STREET

APIES RIVER

EXTERIOR ASSEMBLY AREA

PUBLIC TRANSPORT STOP

EXHIBITION SPACE/ MEETING ROOMS

PUBLIC SEATING SPACE

RECEPTION

COVERED WAITING AREA

VIEWING PLATFORM

ELEVATED WALKWAY

WATER CHANNEL

PUBLIC SEATING AND VIEWING SPACE

CONSTRUCTION AND ASSEMBLY PLATFORM

WORKSHOP/ EXHIBITION SPACE

BUNKER WORKSHOP LEVEL

PRINT SHOP

PRINTERS AND SUPPLIES

GATHERING SPACE

COFFEE SHOP

KITCHEN

INTERNAL SEATING

EXTERIOR WORKSHOP SPACE

KNUCKLE CRANE

STEEL PORTAL FRAME BASE

M3/ NELSON MANDELA DRIVE

EMERGENCY EXIT POINT

AUDITORIUM

LECTURE HALL

EMERGENCY EXIT POINT

FULL LENGTH WINDOW WITH BLINDS

AUDITORIUM FOYER

CIRCULATION SPACE

STAIRS

ELEVATOR

WATER TOWER

BASEMENT PARKING RAMP

RETAINING GABION WALLS WITH VEGETATION BANKS

SLOPING TERRAIN WITH VEGETATION TOWARDS WATER CHANNEL

PUBLIC WALKWAY

WASTE AREA

ACCESS TO WASTE COLLECTION SERVICES

PUBLIC ABLUTIONS

EXTERIOR HUBS AREA

MEN'S BATHROOM

WOMEN'S BATHROOM

WATER STORAGE TANK

CAR AUTO REPAIR SHOP

OCKERSE STREET

PEDESTRIAN BRIDGE

PUBLIC WALKWAY

CAR BATTERY SHOP

CONSTRUCTION COMPANY

CAR REPAIR SHOP

GROUND FLOOR
SCALE 1:200



PUBLIC SEATING AT SOUTHERN BOUNDARY

SA PRIVATE SCHOOL - PRIMARY SCHOOL

PRIVATE PARKING SPACE

JOHANNES RAMOKHOASE STREET

EXHIBITION SPACE/
MEETING ROOMS

APIES RIVER

EXTERIOR ASSEMBLY AREA

PUBLIC TRANSPORT STOP
COVERED WAITING AREA

WATER CHANNEL

VIEWING PLATFORM

ELEVATED WALKWAY

CONSTRUCTION AND ASSEMBLY PLATFORM

PRINT SHOP

GATHERING SPACE

COFFEE SHOP

PUBLIC SEATING AND VIEWING SPACE

EXTERIOR WORKSHOP SPACE

KNUCKLE CRANE

OFFICE SPACE

M3/ NELSON MANDELA DRIVE

AUDITORIUM

CIRCULATION SPACE

STAIRS

ELEVATOR

SLOPING TERRAIN WITH VEGETATION TOWARDS WATER CHANNEL

FULL LENGTH WINDOW WITH BLINDS

AUDITORIUM FOYER

WASTE AREA

RETAINING GABION WALLS WITH VEGETATION BANKS

PEDESTRIAN BRIDGE

PUBLIC ABLUTIONS

CAR AUTO REPAIR SHOP

ACCESS TO WASTE COLLECTOR SERVICES

OCKERSE STREET

CAR BATTERY SHOP

FIRST FLOOR
SCALE 1:200



PUBLIC SEATING AT SOUTHERN BOUNDARY


PUBLIC WALKWAY

CONSTRUCTION COMPANY

CAR REPAIR SHOP

JOHANNES RAMOKHOASE
STREET

SITE NORTHERN BOUNDARY




SITE EASTERN
BOUNDARY

OCKERSE
STREET


APIES RIVER

BASEMENT FLOOR
SCALE 1:200







DETAIL 4 REINFORCED CONCRETE SLAB SECTION
SCALE 1 : 10




DETAIL 5 SUBSOIL DRAINAGE PIPE
SCALE 1 : 5




DETAIL 6 ROOF CONNECTION DETAIL
SCALE 1 : 5




DETAIL 7 RAIN CHAIN
SCALE 1 : 5




DETAIL 1 PAVEMENT PLANTER
SCALE 1 : 5



DETAIL 2 3DCP WALL PLAN DETAIL
SCALE 1 : 5



DETAIL 3 3DCP WALL SECTION
SCALE 1 : 5



STAINLESS STEEL GUTTER EMBEDDED IN GABION WALL WITH DOWNPIPE TO PLANTER

5000 mm WATER CHANNEL WITH GABION WALL THAT SPILLS OUT INTO APIES RIVER

500 mm WIDE GABION WALL WITH PLANTER

CONCRETE PAVERS SLOPING TOWARDS WATER CHANNEL

NGL
WATER LINE

EARTH

RETAINING STONE WALL

REINFORCED CONCRETE STRIP FOUNDATION

250 MICRON DPC WITH 250 mm OVERLAPS

COVERED WALKWAY

KLIP-LOK 406 ECO ROOFING SHEETS OVERLAPPED
 135 mm GLASS WOOL FLEXIBLE BLANKET INSULATION WITH 15 kg/m² DENSITY AND 0.04 k-VALUE OVERLAPPED WITH 50 mm AND FIXED BETWEEN METAL PURLINS WITH ADHESIVE TAPE
 75 x 50 x 20 mm STEEL PURLINS
 240 x 120 x 10 mm STRUCTURAL STEEL I-BEAM
 500 mm WIDE 3DCP WALL WITH METAL ROOF BOLTED TO TOP

WORKSHOP AND EXHIBITION SPACE

5000 x 3000 x 500mm ALUMINUM WINDOW FRAME
 CONCRETE WINDOW CILL

2000 mm WIDE ELEVATED TIMBER WALKWAY OVERLOOKING THE INTERIOR WORKSHOP SPACE

D200 mm CONCRETE CAST-IN-PLACE PIER

250 MICRON DPC WITH 250 mm OVERLAPS

REINFORCED CONCRETE SLAB ROOF OF BASEMENT PARKING

EXPANSION JOINTS

SUNKEN WORKSHOP FLOOR

FLUORESCENT LIGHT
 GALVANISED CABLE TRAY
 FIRE SPRINKLER SYSTEM PIPES ATTACHED TO CEILING

REINFORCED CONCRETE DROP BEAMS

BASEMENT PARKING

REINFORCED CONCRETE COLUMNS


SECTION D-D
 SCALE 1:20

MOVEMENT

PUBLIC USERS



- Community members/visiting individuals can access the site
- Walkways are accessible to all individuals
- Outside seating space and viewing platforms
- Natural spaces on site act as an oasis within the city
- Ablution facilities can be used by all individuals on site



WATER

ABLUTIONS



- Stormwater that falls on built fabric surfaces on site
- Water collected from roofs into gutters and downpipes
- Water is stored in water harvesting tank
- Water pump connected to storage tank sends water to ablutions
- Water closets and hand wash basins receive water


WATER IS COLLECTED FROM ROOFS INTO GUTTERS AND DOWNPIPES



WATER CHANNEL TO RIVER



- Stormwater that falls on built fabric surfaces on site
- Water collected from roofs flow into the gutters
- Water flows down chain drip from gutter
- New water channel anchors chain drip and receives water
- Water flows down into Apies River with vegetation on borders




SECURITY

SURVEILLANCE & ENTRY POINTS




- Passive surveillance provided by CPD attendees and office users
- Entry points at selected spaces - controlled
- Gates are set up at selected entry points that are open during the daytime - closed at night
- Active surveillance by business owners on site - coffee and print shop



WASTE



- Minimal waste from construction at the workshop and waste from the cafe is sent to waste area on site
- Waste is sorted into different containers - recycling occurs on site. Minimal waste is sent away
- Waste collection services come to site. Construction waste material can also be brought to site






PRODUCTION

CPD PROJECTS



- Architects/CPD participants gather at the reception space and view the site from afar
- CPD course commences with lectures and design sessions
- Building of prototypes happen in the workshop towards the river side
- Structures are assembled on site and distributed later



PROGRAMME USERS



- Architects/CPD participants gather at the reception space
- The site is observed from a platform before a walk through
- Lectures in the auditorium commence - EBT information
- Design sessions take place
- Construction of prototype in workshop

